

# The Rare Symmetry Violating Processes Project

**Jonathan Kotcher**  
**BNL HEP DOE Review**  
**27-28 April 2005**  
**Brookhaven National Laboratory**



- **Overview of experiments, AGS**
- **Project timelines**
- **Management, organization**
- **BNL involvement in RSVP**
- **Construction project status, cost summary**
- **Running beams for RSVP: logistics & costs**
- **Brookhaven commitment, base program support**
- **Closing remarks**

**Arizona State University** J.R. Comfort, J. Figgins

**University of British Columbia, Canada** D. Bryman, M. Hasinoff, J. Ives

**Brookhaven National Laboratory** D. Beavis, I.-H. Chiang, A. Etkin, J.W. Glenn, A. Hanson, D. Jaffe, S. Kettell, D. Lazarus, K. Li, L. Littenberg, G. Redlinger, C. Scarlett, M. Sivertz, R. Strand

**University of Cincinnati** K. Kinoshita

**IHEP, Protvino, Russia** G. Britvich, V. Burtovoy, S. Chernichenko, L. Landsberg, A. Lednev, V. Obraztsov, R. Rogalev, V. Semenov, M. Shapkin, I. Shein, A. Soldatov, N. Tyurin, V. Vassil'chenko, D. Vavilov, A. Yanovich

**INR, Moscow, Russia** A. Ivashkin, D. Ishuk, M. Khabibullin, A. Khotjanzev, Y. Kudenko, A. Levchenko, O. Mineev, A. Vasiljev, N. Yeshov

**KEK, Japan** M. Kobayashi

**Kyoto University of Education, Japan** R. Takashima

**Kyoto University, Japan** H. Morii, Y. Nakajima, T. Nomura, N. Sasao, T. Sumida, N. Taniguchi, H. Yokoyama

**University of Montreal, Canada** J.-P. Martin

**University of New Mexico** B. Bassalleck, N. Bruner, D.E. Fields, J. Lowe, T.L. Thomas

**INFN, University of Perugia, Italy** E. Imbergamo, A. Nappi, M. Valdata, M. Viti

**Stony Brook University** N. Cartiglia, I. Christidi, M. Marx, P. Rumerio, R.D. Schamberger

**TRIUMF, Vancouver, Canada** P. Amaudruz, M. Barnes, J. Doornbos, P. Gumplinger, R. Henderson, N. Khan, J. Mildemberger, A. Miller, A. Mitra, T. Numao, R. Poutissou, F. Retiere, A. Sher, G. Wait

**Tsinghua University, Beijing, China** S. Chen

**University of Virginia** E. Frlez, D. Pocanic

**Virginia Polytechnic Institute and State University** M. Blecher, N. Graham, A. Hatzikoutelis



**Yale University** G. Atoyan, S.K. Dhawan, V. Issakov, A. Poblaguev, M.E. Zeller

**University of Zurich, Switzerland** P. Robmann, P. Truol, A. van der Schaaf, S. Scheu

**80 scientists, 10 graduate students,  
19 institutions, 6 countries**

**Spokespersons:  
D. Bryman  
(UBC, Canada),  
L. Littenberg (BNL),  
M. Zeller (Yale)**

See talk by D. Jaffe




- Anticipate 10% measurement of  $B(K_L \rightarrow \pi^0 \nu \bar{\nu}) \sim 3 \times 10^{-11}$ 
  - 5% measurement of area of unitarity triangle (unique)
- Early running provides sensitive probe of non-SM physics

# KOPIO Concept

## **KOPIO: Measurement of $K_L^0 \rightarrow \pi^0 \nu \bar{\nu}$**

### CONCEPTS

- Measure as much as possible:  
Energy, position and *ANGLE* of each photon.
- Work in the C.M. system :  
Use TOF to get the  $K_L^0$  momentum.
- Maximize Photon Veto Efficiency
- Maximize Intensity of Microbunched Beam



### AGS Requirements

#### Proton Beam:

**100 TP/spill**

**4.9 sec spill, 2.3 sec interspill period**

**25 (100) MHz microbunching frequency**

**200 (260) ps bunch width**

**Interbunch extinction  $1 \times 10^{-3}$**

#### Kaon Beam:

**42.5 degree take-off angle**


**Soft momentum spectrum (0.5, 1.5 GeV)**

**$3 \times 10^8 K_L$ /spill**

**10 GHz neutrons**

# KOPIO Experimental Layout

**Project Manager:**  
**M. Marx (SUNY Stony Brook)**



**Spokesman: W. Molzon (UCI)**

## **Boston University**

R. Carey, I. Logashenko, J. Miller,  
B. L. Roberts

## **Brookhaven National Laboratory**

J. M. Brennan, K. Brown, G. Greene,  
L. Jia, W. Marciano, W. Morse,  
P. Pile, Y. Semertzidis, P. Yamin

## **University of California, Berkeley**

Y. Kolomensky

## **University of California, Irvine**

C. Chen, M. Hebert, P. Huwe,  
W. Molzon, J. Popp, V. Tumakov

## **University of Houston**

Y. Cui, N. Elkhayari, E. V. Hungerford,  
N. Klantarians, K. A. Lan

## **University of Massachusetts, Amherst**

K. Kumar

## **Institute for Nuclear Research, Moscow**

V. M. Lobashev, V. Matushko

## **New York University**

R. M. Djilkibaev, A. Mincer, P. Nemethy,  
J. Sculli

## **Osaka University**

M. Aoki, Y. Kuno, A. Sato

## **Syracuse University**

R. Holmes, P. Souder


## **University of Virginia**

C. Dukes, K. Nelson, A. Norman

## **College of William and Mary**

M. Eckhause, J. Kane, R. Welsh


# MECO Scientific Goals



# MECO Experimental Layout

**Project Manager:**  
**M. Hebert (UCI)**


- **1000-fold increase in  $m$  beam intensity over existing facilities**
  - High Z target for improved pion production
  - Axially-graded 5 T solenoidal field to maximize pion capture
  - To eliminate prompt backgrounds,  $< 10^{-9}$  extinction required



- Curved transport selects low momentum  $m^-$
- Muon stopping target in a 2 T axially-graded field to improve conversion  $e^-$  acceptance
- High rate capability  $e^-$  detectors in a constant 1 T field


# MECO Superconducting Solenoids

**Project Manager:**  
**B. Smith (MIT/PSFC)**



PS		TS		DS	
Cryostat	55,800 kg	TSu cryostat	38,200 kg	Cryostat	56,200 kg
Iron	613,000 kg	TSd cryostat	36,600 kg	Iron	794,000 kg
		TS base frame	13,900 kg		
SSC <u>inner</u> cable	31,300 m	SSC <u>outer</u> cable	24,900 m	SSC <u>outer</u> cable	20,700 m

See talk by P. Pile



- **KOPIO:**


- Momentum = 25.5 GeV/c
- Spill length = 4.9 sec
- Rep rate (AGS cycle time) = 7.2 sec
- Intensity = 100 TP/spill
- Time between bunches = 40 nsec
- Beam bunch width = 200 (260) psec RMS baseline goal
- Extinction between bunches =  $1 \times 10^{-3}$

Upgrades to the AGS are driven by experimental requirements to achieve physics goals.

- **MECO:**

- Momentum = 7.5 GeV/c
- Spill length = 0.5 sec
- Rep rate (AGS cycle time) = 1.0 sec
- Intensity = 20 (40) TP/sec base (stretch)
- Time between bunches = 1350 nsec
- Beam bunch width < 50 nsec full width
- Extinction between bunches =  $1 \times 10^{-9}$

# AGS Upgrades for RSVP



# WBS Overview



<b>System</b>	<b>WBS</b>	<b>Fractional Base Cost</b>	<b>Description</b>
<b>Project Office</b>	<b>1.1</b>	<b>11%</b>	<b>Management, oversight of RSVP project, supporting offices at Columbia University and BNL.</b>
<b>KOPI0</b>	<b>1.2</b>	<b>25%</b>	<b>Design, construction, installation and technical commissioning of KOPI0 detector</b>
<b>MECO Detectors</b>	<b>1.3</b>	<b>13%</b>	<b>Design, construction, installation and technical commissioning of external extinction, proton target, muon beam line, and sensitive detector elements for the MECO detector</b>
<b>AGS</b>	<b>1.4</b>	<b>23%</b>	<b>Design, construction, installation and technical commissioning of accelerator upgrade components, beam lines, experimental areas, and integration and infrastructure support</b>
<b>MECO Magnet</b>	<b>1.5</b>	<b>28%</b>	<b>Design, fabrication, installation and technical commissioning of superconducting solenoid system for MECO</b>

**Describes construction project only**

# RSVP Timeline: Overview

- **10/96** – BNL Scientific Approval for KOPIO
- **10/97** – BNL Scientific Approval for MECO
- **11/99** – Submission of RSVP to NSF as MRE candidate
- **07/00** – NSF External Cost Verification Review
- **10/00** – NSF National Science Board authorizes RSVP for inclusion in President's Budget “for funding in FY02 or later”
- **06/01** – NSF External Panel Review (science, cost, technical, management)
- **2001** – HEPAP Subpanel endorses physics goals of RSVP
- **03/02** – NSF External Panel Review (R&D progress, budgets, roadmap)
- **01/04** – DOE (Lehman) Review of RSVP impact on RHIC operations
- **02/04** – NSF proposes RSVP to Congress for FY2006 funding as MREFC
- **09/04** – NSF creates RSVP Project Office, W. Willis, Project Director
- **08/04** – DOE/NSF Interagency MoU signed regarding RSVP
- **12/04** – Congress appropriates \$15M MREFC & construction start for FY05
- **02/05** – President's Budget requests FY06 MREFC funding for RSVP at \$42M
- **03/05** – HEPAP Subpanel on RSVP science value, R. Cahn, LBL, Chair
- **04/05** – NSF RSVP Baseline Review, S. Wojcicki, Stanford, Chair

# RSVP Recent Timeline (1)



<b>Milestone</b>	<b>Date</b>	<b>Status, Comments</b>
<b>Discussion of Baseline Expectations, Timeline with Experiments</b>	<b>September 13, 2004</b>	<b>Completed</b>
<b>MECO Magnet Review</b>	<b>Sun-Tue, Oct 10-12, 2004</b>	<b>Held at Columbia U., MOG, Tom Taylor (CERN), Chair</b>
<b>AGS Review</b>	<b>Thu-Fri, Nov 4-5, 2004</b>	<b>Held at BNL, Ray Larsen (SLAC), Chair</b>
<b>Internal discussion of resource-loaded schedules (RLS) for all projects</b>	<b>Thu, Dec 9, 2004</b>	<b>Held at BNL – Project Office, NSF PM, &amp; experiments</b>
<b>Simulations &amp; Backgrounds Review</b>	<b>Tue-Thu, Jan 11-13, 2005</b>	<b>Held at NYU, Jack Ritchie (UTexas), Chair</b>
<b>Initial review of RLS for all projects</b>	<b>Tue-Thu, Jan 18-20, 2005</b>	<b>Reviewed by LOG, Tom Kirk (BNL), Chair</b>


# RSVP Recent Timeline (2)




<b>Milestone</b>	<b>Date</b>	<b>Status, Comments</b>
<b>All-Hands Baseline Preparation Kickoff</b>	<b>Feb 17, 2005</b>	<b>Focus projects on spring '05 baselining</b>
<b>HEPAP subpanel on RSVP science value convened</b>	<b>March, 2005</b>	<b>R. Cahn, LBL, Chair</b>
<b>Preliminary Baseline Review (Project Office)</b>	<b>Wed-Fri, April 6-8, 2005</b>	<b>Held at BNL, E. Temple (FNAL), Chair</b>
<b>NSF Baseline Review</b>	<b>Wed-Fri, April 20-22, 2005</b>	<b>Held at BNL, S. Wojcicki (Stanford), Chair</b>
<b>Submission of RSVP Project Plan to NSF</b>	<b>May 2005</b>	<b>Package will include initial report from HEPAP subpanel</b>
<b>NSB Decision on RSVP Startup</b>	<b>August 2005</b>	

**This intensive series of reviews represents initial preparatory phase toward achieving a project baseline**

# RSVP Organization & Oversight






- **RSVP International Finance Board (IFB):**
  - Provides oversight for project funding
  - Coordinates, integrates plans for funding and deliverables, as defined through institutional MoU's
  - Review of project funding, governance
  - Functions, roles spelled out in RSVP PMP

# RSVP Project Organization

● = BNL leadership role



- **KOPIO (1.2):**

- **D. Beavis, I.-H. Chiang, A. Etkin, J.W. Glenn, A. Hanson, D. Jaffe\*, S. Kettell, D. Lazarus, K. Li, L. Littenberg, G. Redlinger, C. Scarlett, M. Sivertz, R. Strand**
- **Deeply involved in most activities, including leadership & oversight roles:**
  - **WBS Level 3 Subsystem Managers: Redlinger (DAQ - 1.2.8), Beavis (Systems Integration - 1.2.10)**
  - **KOPIO liaison to AGS, expt'l oversight of AGS modifications: Sivertz**
  - **Simulations: Jaffe**

- **MECO (1.3):**

- **J. M. Brennan, K. Brown, G. Greene, L. Jia, W. Marciano, W. Morse, P. Pile, Y. Semertzidis\*, P. Yamin**
  - **WBS Level 3 Managers: Morse (Muon Beamline - 1.3.3)**
  - **Extinction (Semertzidis), Production Target and Shield, Background Studies (Yamin)**

**Personnel in black are supported off of DOE HEP base funds  
(\* = presenting for experiments in afternoon session)**

- **AGS (1.4):**
  - **AGS upgrades dominated by BNL personnel**
    - **Canadian participation providing major portions to this upgrade**
  - **WBS Level 2 Project Manager: Pile (1.4)**
  - **WBS Level 3 Subsystem Managers:**
    - **AGS/Booster (Brown – 1.4.1)**
    - **Switchyard (Penzick – 1.4.2)**
    - **KOPIO (Pearson – 1.4.3)**
    - **MECO (Phillips – 1.4.4)**
  - **Preceding months have seen major effort associated with development of AGS technical, project plan**
    - **Project plan now quite mature**

**\*Presenting for AGS in afternoon session**

- **MECO Magnet (1.5 ):**

- **MIT is principal institution for MECO Magnet (B. Smith, PM)**
- **MOG strongly recommended increasing BNL role in magnet, being pursued**
- **C-AD developed baseline cost estimate for cryogenic cooling system**
  - **Presented by Tuozzolo (C-AD Chief M.E.) at NSF Baseline Review**
  - **Developed by many, including:**
    - **Bruno, Jia, McIntyre, Nicoletti, Phillips, Tallerico, Tuozzolo**
- **Broader C-AD role under development**

**ossible role for SMD also under consideration. Initial deration. Initial discussions begun in late '04 between Project fffice, Project Manager/MIT, and SMD**

**of cryogenic design, coil/cryostat integration, testing  
coil/cryostat integration, testing  
, Sondericker, Wanderer, others**

# Project Status (1)



- **To date \$12.3M in R&RA funds have been provided to RSVP**
  - **\$6.0M in FY04**
  - **\$2.3M in FY05 supports new Project Office, MECO Magnet**
  - **No substantial sustained support for engineering, etc.**
- **Congressional Omnibus Appropriations bill of Nov '04 provided \$15M in MREFC funds and construction start in FY05**
- **President's Budget request for FY06 contains \$42M for RSVP, and total six-year construction budget of \$158M (FY05\$)**
- **Release of FY05 funds, and construction start, awaits decision from NSB in August. Dependent most heavily on outcome of NSF Baseline Review & HEPAP Subpanel.**

- **Projects have not had benefit of extensive R&D funds**
  - **No opportunity for detailed engineering designs**
  - **Some systems more advanced than others, but all are still either in conceptual stage, or slightly beyond – “between CD1 and CD2”**
- **Construction outlay is understood to include funds for engineering design and development**
- **Given this, approach has been to develop a project plan that includes all currently anticipated needs and costs**
- **Contingencies have been applied that attempt to take into proper account the maturity of the designs**
  - **Risk assessments integrated wherever possible**
  - **Back-up designs considered wherever resources, time permit**
- **All cost, contingency, schedule, and manpower estimates shown are extracted from fully resource-loaded schedules**
- **While these experiments are very challenging, none of the proposed detector or accelerator systems push current limits of technology**

- **MECO Magnet is cost and schedule driver for RSVP**
  - **Single most expensive, technically demanding item**
- **Standing Magnet Oversight Committee (MOG) established to serve in ongoing advisory capacity to Project Director:**
  - **Elwyn Baynham (Rutherford Appleton Laboratory)**
  - **Gene Fisk (Fermilab)**
  - **Herman ten Kate (CERN)**
  - **Tom Taylor, Chair (CERN)**
    - **Now serves as technical advisor to Project Office on magnet**
  - **Akira Yamamoto (KEK)**
- **First review held October 10-12, 2004 at Columbia University**
- **Comments, recommendations geared toward reduction of risks of all kinds**
- **Recommendations being considered, integrated by Magnet Project Team**

- **Jan '05: Project Office agrees to NSF directive to prepare for April baseline**
- **Project Office proposed cost target for RSVP detector construction, which was accepted by agency:**
  - **\$240M in FY05\$, includes 45% total contingency**
- **Cost envelope target based on estimates from individual Project Managers as presented to Project Office in early CY05**
- **Final guidelines to projects from Project Office (burdened FY05\$):**
  - **Project Office: \$20M**
  - **K0PI0: \$55M (NSF portion)**
  - **MECO Detectors: \$24M**
  - **AGS: \$40M**
  - **MECO Magnet: \$56M**
- **Guidance for cost targets includes weighted, risk-based assessment of contingency, based on Lockheed guidelines**
  - **Schedule, cost, technical, design**

# Total RSVP MREFC Cost (AYk\$)

Total RSVP MREFC in AYk\$ (NSF Funding Required)										
	WBS	FY05	FY06	FY07	FY08	FY09	FY10	FY11	FY12	Total
RSVP Project Office	1.1	0.0	3029.2	3107.9	3213.5	3284.3	3369.8	3457.3	0.0	19,462.1
KOPIO	1.2	0.0	7102.3	12377.9	13827.5	7486.1	3526.9	657.7	0.0	44,978.4
MECO Detector	1.3	0.0	4669.1	6952.0	6812.8	2591.7	1478.2	834.7	0.0	23,338.6
AGS	1.4	0.0	9557.0	15284.0	9270.2	5077.8	1875.7	935.3	0.0	42,000.1
MECO Magnet	1.5	0.0	5194.9	9126.6	19484.2	11473.8	4156.0	1733.5	0.0	51,169.0
<b>TOTAL RSVP BASE COST (AYk\$)</b>		<b>0.0</b>	<b>29552.5</b>	<b>46848.4</b>	<b>52608.2</b>	<b>29913.8</b>	<b>14406.6</b>	<b>7618.6</b>	<b>0.0</b>	<b>180948.1</b>
Contingency		0.0	7766.2	19978.6	25567.2	21314.2	8241.1	2895.1	0.0	85,762.4
Contingency (%)		0.0	26.3	42.6	48.6	71.3	57.2	38.0	0.0	47.4
<b>SUB-TOTAL</b>		<b>0.0</b>	<b>37318.6</b>	<b>66827.0</b>	<b>78175.5</b>	<b>51228.1</b>	<b>22647.7</b>	<b>10513.7</b>	<b>0.0</b>	<b>266,710.6</b>
Pre-operations		0.0	0.0	0.0	0.0	0.0	4934.5	0.0	0.0	4,934.5
Engineering & commissioning		0.0	0.0	0.0	0.0	0.0	0.0	5378.6	5124.9	10,503.5
<b>TOTAL RSVP MREFC (AYk\$)</b>		<b>0.0</b>	<b>37,318.6</b>	<b>66,827.0</b>	<b>78,175.5</b>	<b>51,228.1</b>	<b>27,582.1</b>	<b>15,892.3</b>	<b>5,124.9</b>	<b>282,148.5</b>
escalation rate		1	1.0280	1.0547	1.0822	1.1103	1.1392	1.1688	1.1991	

- **NSF exposure for RSVP construction - in-kind, other contributions removed**
- **Total MREFC (AYS) = \$282.15M**
  - **Detector Construction: \$266.71M**
  - **Pre-operations, Commissioning: \$15.44M**
- **Total project contingency includes contingency on in-kind contributions**
- **MREFC only, R&RA not included (beam and detector R&D, operations)**

- **Recommendations from Executive Summary of Simulations & Background Review (NYU, Jan 18-20, 2005, J. Ritchie, Chair):**
- **KOPIO should “as soon as possible”:**
  - **Develop a fully engineered design for the barrel photon veto, build a full-scale prototype, and subject it to beam tests to validate that it achieves the required performance.**
  - **Perform tests with the AGS to measure beam microbunch width and inter-bunch extinction at full intensity (at least 70 Tp/spill) and to demonstrate the necessary bunch widths and extinction are achieved.**
  - **Design the neutral beam and shielding, install it, and perform beam tests (using specialized detectors) to establish that the properties of the beam (e.g., n halo) meet the requirements of the experiment.**
- **MECO should “as soon as possible”:**
  - **Perform tests with the AGS to demonstrate the required extinction when running at 8 GeV with intensity of at least 20 Tp/spill.**
- **Overall recommendation:**
  - **Also, both KOPIO and MECO should benefit if data-taking is structured to provide the longest possible runs in alternate years, rather than shorter runs based on an equal division of available running each year.**
- **We agree with and accept these recommendations, and have included it as an integral part of our project plan**
- **The plan is constructed in order to allow us to quantitatively characterize AGS beams (neutral beam, extinction) as quickly as technically and logistically feasible**

- **Three relevant running scenarios:**
  - **Without RHIC running**
  - **With RHIC running heavy ions**
  - **With RHIC running polarized protons**
- **Cost and requirements for running in each of these scenarios is different, and has been considered in great detail. Every attempt has been made to include all relevant items:**
  - **C-AD personnel**
  - **Cryogenics, power, waste disposal, etc.**
  - **Maintenance of MECO magnet**
  - **Experiment-specific running costs**
    - **Tapes, media, cables, chamber gases, supplies, shipping, etc.**
  - **Maintaining scaled-back Project Office in post-construction years**
- **While out years cannot be predicted with any accuracy, project plan has assumed running scenarios that are as reasonable as any other**

- **Beam and detector R&D (R&RA):**
  - **8 weeks in each of FY08 and FY09**
    - **Neutral beam/halo**
    - **Extinction tests for MECO**
    - **Beam tests for completed portions of detectors**
- **Beam Pre-operations (MREFC):**
  - **8 weeks in FY10**
  - **Neutral beam/halo with micro structure**
    - **25 MHz cavity installed summer 2009**
  - **Pushing extinction tests to higher intensity for MECO**
  - **Beam tests for completed portions of detectors**
  - **Prepare for engineering/commissioning and operations running**
- **Engineering and commissioning (MREFC)**
  - **8 weeks in FY11 (K0PI0)**
  - **8 weeks in FY12 (MECO)**
- **Operations, data-taking (R&RA):**
  - **17 weeks in FY11 (K0PI0) and FY12 (MECO)**
  - **25 weeks in FY13-16 (alternating K0PI0, MECO)**

Funding categories follow NSF guidance

# Summary of RSVP Beam Costs



	Exp't	Weeks	Cost (Ayk\$)
<b>R&amp;D</b>			
FY08	Both	8	4,687.6
FY09	Both	8	4,809.3
<b>TOTAL R&amp;D</b>		<b>16</b>	<b>9,496.9</b>
<b>Pre-ops &amp; Eng/Comm</b>			
FY10	KOPIO	8	4,934.5
FY11	KOPIO	8	5,378.6
FY12	MECO	8	5,124.9
<b>TOTAL Eng/Comm</b>		<b>16</b>	<b>15,438.0</b>
<b>Operations</b>			
FY11	KOPIO	17	13,666.2
FY12	MECO	17	13,185.7
FY13	KOPIO	25	22,864.2
FY14	MECO	25	21,462.9
FY15	KOPIO	25	23,600.2
FY16	MECO	25	22,112.9
<b>TOTAL Operations</b>		<b>134</b>	<b>116,892.1</b>

**Operations cycle provides 3.7E20 integrated TP to MECO, 5700 hours running time at 100 TP equivalent for KOPIO. Takes into account losses due to startup times, intensity build up, etc.**


**Start of commissioning and operations takes into consideration nominal detector readiness dates.**

# RSVP Cost Summary (AY\$)



- **Detector and AGS construction (MREFC):**
  - **TOTAL: \$266,711k**
- **Pre-operations and engineering (MREFC):**
  - **Pre-operations: \$4,934k**
  - **Engineering & commissioning: \$10,504k**
  - **TOTAL: \$15,438k**
- **Total MREFC = \$282,149k**
- **Beam and detector R&D, operations and D&D (R&RA):**
  - **Beam and detector R&D: \$9,497k\$**
  - **Operations: \$116,892k**
  - **D&D: \$19,600k**
  - **TOTAL: \$145,989k**
- **Total R&RA = \$145,989k**

# RSVP Summary Schedule



L1 Milestones

R&D

Preops, eng.

Ops

Construction

Running with Beams

KOPIO

MECO Detectors

AGS Upgrade

MECO Magnet

# RSVP Level 1 Milestones



<b>RSVP Level 1 Milestones</b>		
Milestones	Baseline Date	Date with Contingency
All Solenoid Procurements Placed	01/23/08	07/23/08
MECO A Line Ready for Tests	10/01/08	04/01/09
K0PI0 Neutral Beam Line Complete	12/01/08	06/01/09
K0PI0 Experiment Complete and Ready for Beam	10/01/10	05/01/11
MECO Experiment Complete and Ready for Beam	05/19/11	01/19/12


**MECO Magnet is critical path item for RSVP**

# Labor Profile by Resource Category


**Physicist effort is included, but not costed, in project plan**

**MECO Detectors. WBS 1.3**

**Total of over 200 institution-specific labor categories, associated rates & overheads**




**RSVP FTEs\_Technical**



# Total Manpower Needed, by Project



**RSVP Total FTEs**



- **As noted in NSF Baseline Management Sub-Committee\* closeout report last week, RSVP is embedded in an unusual management situation:**
  - **An NSF project at DOE laboratory using a DOE accelerator facility**
  - **Shared agency responsibility for funding the accelerator facility**
  - **Brookhaven is “host” laboratory but is not a sponsor of project**
  - **DOE is not a direct sponsor of the project**
  - **The RSVP project itself is very complex with project offices at Columbia and BNL and 4 almost “stand-alone” subprojects to be integrated into a unified project**
- **The management of RSVP is an experiment in itself, and has succeeded thus far due in large part to the good will and positive actions on the part of all of the principal partners**

**\*J. Marx (LBL – Sub-Committee Chair), J. Butler (FNAL),  
S. Wojcicki (Stanford – Committee Chair)**

- **BNL has defined and strengthened its commitment to RSVP in recent months. As pointed out by the Baseline Committee:**
  - **BNL management seems engaged and committed to success of RSVP**
  - **Director and AD for HENP working to find ways to enhance likelihood of success**
  - **AGS management is actively engaged in providing for needs of RSVP**
  - **BNL management must continue to be engaged and committed to success over life of RSVP**
- **Project Office agrees, and is encouraged by this development**
- **Baseline Committee also stated that DOE should:**
  - **Assure success of AGS project activities**
  - **Provide adequate support for BNL scientific involvement in RSVP (host lab collaborators bring great value to an experiment)**
- **The Project Office considers strong RSVP scientific and technical presence at Brookhaven to be an integral ingredient for success**
- **We are relying on such support as the project makes the transition through approval to construction start**

# Closing Remarks

---

- **RSVP experiments represent exciting physics, among the most cogent probes of the sensitivity frontier the field has to offer**
- **Will lay the foundation for a first-rate physics program that will operate well into the next decade**
- **Laboratory has demonstrated its support, and its intention to do whatever it can to ensure its success. This ingredient is essential, and must continue throughout the project's lifetime.**
- **BNL participation is strong, but will need to grow significantly as the project moves toward construction**
- **Project personnel, experimenters are extremely enthusiastic and dedicated to this enterprise, eager to begin mounting these projects, building the detectors, extracting the science**

# Backup Slides

---



- **Technical**
  - Change the PS from bath to conduction cooled
  - Reduce the number of coils
  - Make test windings to validate conductor, winding and insulation technologies
  - Reduce the number of power supply circuits, and conductors, if possible
  - An all-analog quench detection system was recommended in place of the digital system proposed
  - Conduct a failure analysis of the magnet
  - Design and start construction of tooling for a full scale model test coil
- **Schedule**
  - Schedule is tight
  - More time should be allocated for the contract process
  - Time for model coil work should be included
  - Time for installation and commissioning appears to be short
- **Cost**
  - Allocation of 10% to profit appears low
  - Labor rates look low
  - Cost is based on 2004 prices; should be changed to 2006 prices
  - Purchasing overhead at 15% appears low
- **Management**
  - Risk in attempting award to a single vendor is too high; buy in parts (greater number of procurements)
  - Carry out industrial studies through an RFI
  - Strengthen the team at MIT for design and procurement; keep the technical work there
  - Increase the role of BNL since the magnet will be installed, commissioned and operated there

# Project Tools

- **RSVP using same project tools as US ATLAS**
  - **MS Project for schedule & cost**
  - **For now, using EXCEL for WBS dictionaries, complementary cost information**
    - **ACCESS will be implemented for additional cost tracking, WBS dictionaries/definitions, etc.**
  - **Technical & financial monthly status reports highly automated**
  - **Building web-based interface (including to ACCESS) to facilitate remote project tracking**
- **This has allowed for efficient, timely project ramp up**
  - **Much BNL infrastructure, expertise exists in use of these tools**
  - **Proven successful application in US ATLAS, agencies have signed off on their use, output**
  - **New tools would require major reinvestment in time, money, personnel, gains questionable. Resources more wisely spent elsewhere in project.**
- **Have opted to upgrade from MS Project 2000 to 2003**
  - **Earned value calculated directly in MS Project by Project Office, will be used for reporting**

# Development of Project Plan (1)




- Schedules are resource-loaded
- Subsystem (WBS Level 3) and Project (WBS Level 2) Managers have constructed their schedules themselves, integrating guidance from the Project Office
- Appropriate rates and burdening for various labor categories applied inside MS Project, by institution
- Escalation done external to MS Project
  - For this review, Level 2 and 3 Managers will report in FY05\$ only
  - AY costs presented by Project Office
- Physicists are included as resources in project plan
  - Used to identify labor need only – not costed in project
- Risk-based contingency analysis is applied
  - Lockheed formula

	Project Office	K0PI0	MECO Detectors	AGS	MECO Magnet	TOTAL
Approx. lines in schedule	3	1420	910	3490	970	6793

- **Examples of elements provided to Committee:**  
([http://rsvp.bnl.gov/Project\\_Office/Reviews/RSVPBRApr2005.htm](http://rsvp.bnl.gov/Project_Office/Reviews/RSVPBRApr2005.htm))
  - **Conceptual Design Reports**
  - **Project Management Plan**
  - **RSVP MoU Template**
  - **WBS dictionaries, bases of estimate**
  - **Backup cost books**
  - **Risk assessments**
  - **Cost summaries**
  - **Schedules in MS Project (mpp) format**
  - **Plenary and breakout presentations**
  - **Reports, presentations from previous reviews**
- **In addition to the plenary presentations, talks from the WBS Level 3 subsystem managers have been selected for presentation at the breakouts**
  - **Some additional talks from the Level 3 Managers are also available for presentation (see Project Managers at breakout sessions)**

# Contingency Discussion (1)

- **Lockheed Guidelines, applied by Level 2 and 3 managers, result in 24% contingency.**
- **Includes only partial consideration for delays**
- **Average value for delay in large Federal Projects is 33% (see fig)**
  - **Funding delays, other difficulties**
- **Would result in estimated 20% increase in cost for delays alone**



# Contingency Discussion (2)



- **Preliminary Baseline Review Committee (April 6-8, 2005) could not agree on appropriate contingency for RSVP. Non-management sub-committees felt that 45% overall was appropriate.**
- **However, Management Sub-Committee (G. Bock, T. Elioff, E. Temple [Committee Chair], R. York) disagreed, and recommended 60-70%. Among the reasons unique to RSVP (from report):**
  - **Lack of Laboratory “backstopping”**
  - **Complicated, unproven management and funding structure**
  - **In past, for projects at this early stage (CDR) that were “backstopped” by a Laboratory and mounted in better budget climates, the estimates used to be 50%**
- **U.S. Atlas and DZero Run IIb Upgrade were both held at 45% contingency at baselining. This level of contingency appears to have been sufficient in these cases.**
- **With all of the above in mind, we have proposed 45% contingency, with the expectation that it will be sufficient to subsume a reasonable level of project risk.**

# RSVP Construction Costs (FY05k\$)



RSVP Detector Construction Costs (FY05k\$)						
	Base Cost	Cont (%)	Cont Cost	Sub-Total	In-Kind	TOTAL
<b>RSVP Level 2 Roll Up</b>	<b>179,281.2</b>	<b>23.92</b>	<b>42,891.47</b>	<b>222,172.62</b>	<b>11,395.83</b>	<b>210,776.79</b>
RSVP Project Office	17,737.0	11.00	1,951.07	19,688.06	0.00	19,688.06
KOPIO	53,218.9	28.00	15,043.96	68,262.88	11,395.83	56,867.05
MECO Detector	21,774.7	23.84	5,190.38	26,965.13	0.00	26,965.13
AGS	39,374.2	24.00	9,588.33	48,962.57	0.00	48,962.57
MECO Magnet	47,176.2	23.57	11,117.73	58,293.98	0.00	58,293.98
<b>Project Contingency</b>		<b>20.60</b>	<b>36,138.81</b>			
<b>TOTAL RSVP (FY05k\$)</b>	<b>179,281.2</b>	<b>45.04</b>	<b>79,030.3</b>	<b>258,311.4</b>	<b>11,395.8</b>	<b>246,915.6</b>

- **Level 2 roll ups from Project Managers**
- **Lockheed contingency guidelines applied**
- **Additional project contingency introduced top down from Project Office to realize 45% total**
- **Overall cost within 2% of target**
- **Scrubbing of schedules, reconsideration of designs, further simulations continue in earnest in the effort to realize individual project cost targets**
- **Costs for pre-operations and engineering runs not included**

KOPIO Foreign Contributions (FY05k\$)	Base	Cont	TOTAL
Canada	5,899	0	5,899
Japan	3,151	658	3,809
Zurich	864	0	864
Russia - INR	824	0	824
<b>TOTAL</b>	<b>10,738</b>	<b>658</b>	<b>11,396</b>

- The D&D plan for RSVP is to restore the AGS floor to the pre-RSVP condition within a reasonable number of years after the end of experiment operations
- It is recognized that the experiments will generate significant amount of beam activated components that will have to be disposed of, and a 2-3 year “cool-down” period will be required before D&D can begin:
  - The slow beam transport will decommissioned
  - All commonly reused valuable equipment such as magnets will be stored
  - The cost of removing and disposing of the experiments will be included
  - Shielding under 5mr will be left in building 912
  - All concrete floor areas over 5mr will be removed and replaced, but no radioactive soil remediated
  - Power and water modifications for RSVP will be removed except where considered an upgrade to existing utilities
  - The AGS and Booster will remain operational for RHIC when RSVP is complete
- Current estimate puts cost at \$19.6M in AY\$, includes 25% contingency.

# RSVP Major Procurements



Major Procurements (FY05k\$s)				
Subsystem	Level 3 WBS	Description	Amount	Schedule
KOPIO	1.2.2/Preradiator	Cathode Electronics Readout Cards	1,233.5	January-06
		Anode Electronics Readout Cards	827.6	January-06
	1.2.3/Calorimeter	Photon Calorimeter APD	938.4	October-06
	1.2.6/Catcher	Purchase PMT - 5 inch	735.0	July-06
	1.2.8/DAQ	Trigger Procurement	1,052.4	Apr 2008 (25%), Apr 2009 (75%)
MECO	1.3.2/Production Target and Shield	Tungsten Alloy Billets for the Heat Shield	1,389.0	October-05
		Copper Castings for the Heat Shield	734.6	December-07
	1.3.5/Electron Calorimeter	Large Area Photodiodes	1,247.0	December-06
		Lead Tungstate Crystals	1,070.0	December-06
AGS	1.4.1/Booster/AGS Modifications	ES&H Cap Contract	2,201.6	July-07
		100MHz Cavity Procurement	570.0	June-08
	1.4.3/KOPIO	Steel Shielding	741.0	March-08
		Steel & Coils	537.5	April-07
		Detector Pit Construction Contract	536.9	April-07
Magnets	1.5.2/Magnet System Fabrication	DS Magnet	5,145.6	August-07
		TSu Magnet	4,612.5	November-07
		PS Magnet	4,418.9	January-08
		TSd Magnet	4,237.5	November-07
		Magnet Tooling Fabrication	5,004.0	June-06

# Schedule Methodology

- Schedules contain no explicit float – reflect nominal duration for completion
- In order to do everything possible to keep pace, we intend to manage to this aggressive schedule
- Four tiers of schedule milestones are being constructed:
  - Level 4, held by sub-system managers to track their projects
  - Level 3, held by WBS Level 2 Project Managers
  - Level 2, held by Project Office
  - Level 1, held by NSF
- Milestone selections, and hierarchical assignments, in progress
- Explicit float added to Level 1 milestones that describe anticipated schedule contingency
  - 15%, but not less than 6 months
    - Early ramp up is most difficult period - we will gain in momentum, personnel, understanding how to manage ourselves more effectively
    - Contingency back-end loaded to ameliorate delays
- Production Readiness Reviews also being incorporated

# Example Level 2 Milestone Candidates




Candidate KOPIO Level 2 Project Director Milestones		
WBS	Name	Baseline Date
1.2.1	<b>KOPIO Vacuum Subsystem</b>	
	Deliver Vacuum Windows to BNL	7/8/08
	Deliver D-4 Vacuum Box to BNL	4/2/08
1.2.2	Deliver Veto Vacuum Tank to BNL	7/24/09
	<b>Preradiator</b>	
	Chamber Production Complete	6/30/09
	Scintillator Proto Sys Complete	12/31/09
	Complete PMT/Base/Preamp/Cable Sys.	12/31/09
	Complete Electronic Readout Sys	9/30/09
	Complete External PV Sys.	12/31/08
	EPV Electronics Install Complete	12/31/09
1.2.3	Preradiator Install Complete	12/31/09
	<b>Calorimeter</b>	
	Photon Calorimeter Module Prod Assembly Complete	11/26/08
	Module Instrumentation APD Assy Complete	11/26/08
1.2.4	Mechanics Fabrication Complete	11/26/08
	Cabling Subsystem Installation Complete	3/31/10
	<b>Charged Particle Veto</b>	
	Barrel Charged PV Arrival at BNL	5/30/08
	Downstream Charged PV Ready for Installation	6/30/08
1.2.5	FE Electronics & Cabling System Test Complete	6/30/09
	CPV Complete	3/31/10
	<b>Photon Veto</b>	
	UPV Cabling Subsystem and Installation Complete	3/31/10
	BPV Cabling Subsystem and Installation Complete	3/31/10
	MPV Mechanics Assembly Complete	4/15/08
	MPV Cabling Subsystem and Installation Complete	3/31/10
DSPV Cabling Subsystem and Installation Complete	3/31/10	
MCPV Cabling Subsystem and Installation Complete	3/31/10	

**Work in progress**

# Total Physicists Needed, by Project



RSVP FTEs\_Physicists



**KOPIO In-kind  
(Canada)**

# Change Control (from PMP)




	<b>Level 1: DOE/NSF Joint Oversight Group</b>	<b>Level 2 NSF Program Manager</b>	<b>Level 3 RSVP Project Director</b>
<b>Technical</b>	<b>Changes to the project purpose or goals.</b>	<b>Changes to the baseline list of deliverables.</b>	<b>Changes that do not affect a Level 1 or Level 2 control item.</b>
<b>Cost</b>	<b>Changes to the Total Project Cost.</b>	<b>Changes to the Level 2 cost baseline.</b>	<b>Changes to the cost baseline at WBS Level 3.</b>
<b>Schedule</b>	<b>Greater than 6 month change on a Level 1 milestone.</b>	<b>Greater than 3 months on a Level 1 milestone</b>	<b>Any change in a Level 2 milestone.</b>

# Outline of Funding Flow for RSVP

- **Columbia University is the Host University for RSVP**
- **Funds for K0PI0 (1.2), MECO Detectors (1.3), and MECO Magnet (1.4) will be written to Columbia via a cooperative agreement between Columbia and NSF**
- **Funds will be distributed from Columbia to SUNY Stony Brook (K0PI0), University California, Irvine (MECO Detectors), and MIT (MECO Magnet) via MoUs according to the need outlined in the RLS, with final amounts determined by the Project Office**
- **Subcontracts for the work associated with various sub-detectors will be written from these respective institutions**
- **Invoices must be approved by Project Office prior to payment**
- **Preferred transfer of funds for work done at BNL is via direct transfer through a DoE/NSF interagency agreement**
- **Fallback option would be to treat it in manner identical to the other three primary institutions**

# RSVP Funding Flow



# Cost of an Example Operations Year



- **Example costs for one year of operating MECO for 25 weeks in 2014:**
  - **10 weeks concurrent with RHIC heavy ion running**
  - **5 weeks concurrent with RHIC polarized proton**
  - **10 weeks stand alone (without RHIC)**

<b>EXAMPLE OPERATIONS YEAR: 25 WEEKS MECO RUNNING IN 2014 (FY05k\$)</b>		
<b>AGS COSTS</b>		
Personnel	2,026	
Other Costs*	6,439	
Indirects	3,815	
<b>TOTAL AGS</b>	<b>12,280</b>	
<b>EXPERIMENT-SPECIFIC COSTS</b>		
Seven Technicians (shared)	1,232	
Three Engineers (shared)	708	
Running costs**	1,050	
<b>TOTAL EXPT-SPECIFIC COSTS</b>	<b>2,990</b>	
<b>TOTAL PROJECT OFFICE***</b>	<b>1,733</b>	
<b>TOTAL OPERATIONS (FY05k\$)</b>	<b>17,003</b>	
Inflation Factor	1.26234	
Inflation (k\$)	4,460	
<b>TOTAL COST AYk\$</b>	<b>21,463</b>	
* Shift differential, power, DTS, MSTC, SP, MECO Magnet, etc.		
** Tapes, computers, cables, gases, shipping, visitor support, office supplies, etc.		
*** PD, Deputy, 1 Budget Officer (shared), 2 AAs, 0.5 Scheduler, travel, reviews, etc.		

# Subset of Time-Ordered Milestones for AGS



**AGS Project contains 252 total milestones**  
**Well cover the time interval, allow for close project tracking**

		RSVP AGS UPGRADES PROJECT																			
ID	WBS	Name	2006				2007				2008				2009				2010		
			Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2			
101	1.4.2.6.6.7	A & B line magnets ready																			7/2
69	1.4.4.5.9	PS controls ready for integration																			7/10
63	1.4.1.3.4.6	Design complete																			7/15
334	1.4.4.2.8.4.1	RFMM Hut Requirements Defined																			7/18
186	1.4.2.9.3.2.19	Final test																			7/27
104	1.4.1.3.2.1.10	Procurement Complete																			8/1
35	1.4.4.3.1.2	External Profile Monitors Complete																			8/1
93	1.4.4.3.1.6	Beam Position Monitors Complete																			8/1
54	1.4.1.2.2.2.9	Design Frozen																			8/3
19	1.4.1.3.2.4.7	Procured Parts Delivered																			8/8
93	1.4.1.2.2.1.10	Procurement Complete																			8/9
593	1.4.3.7.2.3	KOPIO Detector pit complete																			8/20
77	1.4.4.4.5.4	Hardware Install																			8/27
7	1.4.1.4.1.2.5	System Ready for Test in AGS																			9/1

# Beam Operations Program Summary



**Program outline, including intensity goals, for beam & detector R&D, pre-operations, commissioning, and operations**

<b>Fiscal Year</b>	<b>Running Activity</b>	<b>Duration (weeks)</b>	<b>Begin (end) intensity goals</b>
2008	Beam/Detector R&D	8	0.2 TP/pulse: Limit activation, not all hardware installed
2009	Beam/Detector R&D	8	same as above
2010	Pre-operations: KOPIO neutral beam, MECO extinction	8	15 TP/pulse max KOPIO 10 TP/second max MECO
2011	KOPIO Engineering	8	10 (30) TP/pulse
2011	KOPIO Operations	17	30 (75) TP/p
2012	MECO Engineering	8	2 (10) TP/second
2012	MECO Operations	17	10 (17.5) TP/s
2013	KOPIO Operations	25	75 (100) TP/p
2014	MECO Operations	25	17.5 (20) TP/s
2015	KOPIO Operations	25	100 TP/p
2016	MECO Operations	25	20 TP/s
<b>TOTALS:</b>			
<b>16 WEEKS BEAM/DETECTOR R&amp;D</b>			
<b>8 WEEKS PRE-OPERATIONS</b>			
<b>16 WEEKS ENGINEERING/COMMISSIONING</b>			
<b>134 WEEKS OPERATIONS</b>			