

# Magnet Performance & RHIC Commissioning

---

Facility Overview

Magnet Acceptance/Ring performance

Pulsed Magnets/Helical Dipoles

Machine Optics

Dynamic Effects

Operating experience

Conclusions

# The Relativistic Heavy Ion Collider Facility Overview

RHIC:  
Two independent  
superconducting rings, 4 km  
each. 6 collision points

## Arc/Matching Sections

Dipoles, 8 cm (288) 3.5T,  
CQS Assemblies, 8 cm (420)  
72T/m  
produced in industry

## Interaction Regions

IP Quads, 13 cm (96)  
IR Dipoles, 10 cm (24)  
IR Dipoles, 18 cm (12)  
produced at BNL



Engineering run 99 (beams circulate),  
Commissioning run 00 (beams collide),  
Physics run in progress 01/02 (35% design  
luminosity)


# RHIC Arcs & IP's

---



# RHIC - Magnet Testing/Ring Performance

- Arc magnet performance established by cold testing only a subset of the magnets (first 10% + 1-in-10)
- All IR magnets cold tested
- Field quality from warm measurements good enough for qualification (few tens of a unit)



Commissioning experience was essentially as expected from the cold testing:

- No arc magnet quenching.
- Training from the IP 18cm dipoles only

**All magnets operated successfully to design energy !**

# RHIC - Magnet Acceptance

---

Given the cost of an accelerator magnet, magnet acceptance is generally a delicate dance between project management <-> accelerator physics with magnet builders caught in the middle.



RHIC magnet field quality 'very good' - systematics rather than randoms dominated:

- some dipole sorting on transfer function
- sextupole quench current determined focusing location
- complex field quality assessment made to determine the best IP quadrupoles for the highest luminosity IR's
- some simple sorting on dipole field quality ( -ve  $b_3$  next to a +ve  $b_3$ )

No magnets were rejected at all. Occasionally elements were assigned as spares.


# RHIC - fast pulsed quadrupole magnets

Pulsing the machine optics; a transition jump to rapidly cross an unstable region caused by the loss of RF phase focusing. Standard RHIC (superconducting) correction quadrupoles



$\pm 40\text{A}$  in 30ms.  
 $dI/dt$  up to 4 kA/s in a low field environment


# RHIC - fast pulsed quadrupole magnets



Transition crossing 'mountain range' plot - turn by turn longitudinal profile

# RHIC - Polarized Protons/Helical Dipoles

---



Four Helical dipoles, 4T, 2 m long, & 360° Twist in each Siberian Snake/Spin Rotator

The Siberian Snakes have been operated but no significant polarised proton running yet


# RHIC - machine optics/orbits

Comparison of  
Measured Orbit  
Deviation from a  
Small Vertical Kick


vs.,

Predicted Deviation  
Based on the Design  
Optics

Excellent agreement



# RHIC - machine optics/beta functions



Beta functions are the closed solutions to the ensemble of quadrupole focussing strengths (effectively the relative beam sizes at the various locations)

Blue lines are the model, open circles are the measurements

1000 point turn by turn at each position monitor


**Machine model and RHIC agree very well. (~ 5%)**

# RHIC - machine optics/coupling


- Coupling is the 'mixing' of horizontal and vertical planes inside the machine and is determined primarily by the orientation of the quadrupole field.

Large closed horizontal offsets across the IP's and look at residual vertical offsets in the rest of the machine after calculated corrections

Coupling from the triplets agrees quantitatively with predictions (field quality & survey) but not in detail





# RHIC - machine optics/coupling



Coupling in the arc sections is measured by looking at minimum tune separation between planes after local compensation of the IP's.

Measured coupling in the arcs agrees well with the predictions


# RHIC - Dynamic effects/persistent currents



Measured and predicted time varying chromaticity.  
Qualitative agreement but large magnet to magnet variations preclude accurate projection. Why is the shape different?  
LHC must do better than this

# RHIC - Dynamic effects/quad focusing

Blue Horizontal Tune (effectively the ratio between integrated quad and dipole fields) stable to 1 in  $10^4$ . Not good enough !



Maintaining ~60 quad circuits (single elements & strings) in synchronism during dynamic processes (acceleration or lo-beta squeeze) can be difficult. More of a power converter issue than a magnet one

# RHIC - Operating Experience

---

Operating experience with the magnet system to date has been good. After the initial engineering run shakedown there has been no major magnet failure (electrical or mechanical)

The magnets are essentially cryostable at injection energies but will (and have) quench at top energies. No damage during quenches.

There has been a small number of voltage taps opened up.

One shorted cable in a low current bundle.

One failed pulsed quadrupole which has been removed (with its twin) from the circuit.



# Magnet Performance & RHIC Commissioning - Conclusions

---

- 'Individual' magnet performance has been as expected e.g. quench.
- 'Ensemble' magnet performance as expected in the arcs but not as good agreement in the IP's (it would appear we understand magnets better than cryostats!).
- Complete cold testing did not prove necessary on the high volume elements
- Magnet reliability has been good to date