Homestake Underground Laboratory

David Berley University of Maryland March 4, 2004

Homestake: What's New?

- NSF to announce process:
 - Consideration of underground lab(s)
 - March 29 meeting at NSF
- Major obstacles at Homestake overcome:
 - Agreement exists for acquisition of Homestake mine
 - Liability issues solved by state of SD
 - \$10 M\$ liability fund and insurance
 - Science Laboratory proposed
 - Mechanism for Cooperation between SD and scientists
- Homestake ready to go!
 - Letter of intent by March 29


Homestake

- A Deep Laboratory dedicated to science
 - Accommodates all experiments requiring great depth
 - Physics
 - Geoscience
 - National Security
 - Outreach and Education
- Staged Approach to lab construction
 - Infrastructure
 - South Dakota (Governor Rounds, Gowen)
 - Science Laboratory
 - NUSL Collaboration (Marshak PI, Lesko Spokesperson)

Model Organization

Science Laboratory and


South Dakota Science & Technology Authority




State of South Dakota

- Conceptual Design of Infrastructure Laboratory
- South Dakota Science and Technology Authority
 - Own, Construct and Operate Infrastructure Lab
- Agreement with Homestake Mining Company
 - Acquisition of mine
 - Indemnification of Homestake
- Appropriated \$24 million
 - Acquisition and refurbishment of the mine

Elevation View of Homestake






Buildings Near the Yates Shaft




3/2/2004


Yates Cage Hoist




Elevation View of Homestake




Infrastructure Laboratory 7100L 7400L 7700L



Homestake Laboratory (Near Term)




Mega-Detector - UNO



Megaton Modular Multi-Purpose Detector

✓ Modular Configuration


Mark A. Laurenti



Megaton Modular Multi-Purpose Detector

✓ Estimated Timeline


Year Four



Brookhaven 040303


15

Addition of Mega-Detector



Baselines to various deep sites

San



Brookhaven 040303

Homestake Flooding

- Shutdown of Homestake, June 2003
 - Flooding at 700 GPM
 - At 4850 L ~ May 2007
 - At 5300 L ~ May 2006
- Dynatec Engineering Report
 - Maintenance of Mine Stability
 - Low water acidity
 - Equipment Damage or Replacement
 - Submerged mechanical and electrical equipment believed repairable but, conservatively, will be replaced
 - Operating Approval for water disposal required
 - Low water impurity content (albeit warm)
 - Preservation of Rock Mass
 - Integrity of high quality rock mass will not be compromised

Homestake Flooding

NSF Reviewer Comment

- I've read the short report by Dynatec about the effects of flooding and am in agreement with the general assessment.
- There is always some deterioration of the "tunnel" walls...
 There will be some clean-up as a consequence, not at all unusual.
- The conservative cost view of replacing any equipment that becomes submerged is wise...
- [T]he operating approvals should be "routine" because of the long history of mining at the site (unlike problems that could arise in a "greenfield").
- Their experience with rock mass stability during dewatering of other mines flooded for short and longer periods of time is also what I would expect, that is, no great instabilities or "caveins". I and the other "DUSEL" panel members arrived at the same conclusion earlier this year.

Schedule for Underground Infrastructure

Homestake

Assumption:
Dewatering Begins
May 2006

Major System Tasks	Scheduled	
	Completion	
	(Months	
	after start)	
Detailed Engineering (begin)	0	
Detailed Engineering (complete)	3	
Yates rehab (begin)	4	
Ross begin rehab (begin)	4	
# 6 Winze (begin)	6	
Dewatering (begin)	7	
Basic Facility Construction (begin)	15	
Yates (complete)	18	
7400 ft Level Construction (begin)	20	
# 6 Winze (complete)	21	
Ross complete rehab	21	
Dewatering (complete)	21	
Basic Facility Construction (complete)	26	
Conversion (Complete)	32	

Cost Scenario for Infrastructure Lab

Dynatec estimate

•	Underground Infrastructure	94M\$
	Dewatering5.8 M\$	
•	Surface Buildings	4
•	Transfer costs (indemnification, transfer)	20
•	Bonding (optional for 5 years)	8
	 Forward Funding over 5 years 	
•	Total Infrastructure Constr.	126
	 State of SD appropriation 	24.3
	 NSF Request over 5 years 	102
•	Outyear Operating Costs	8.1/year

Advantages of Homestake

- Site available Immediately
 - Site acquisition terms negotiated
 - Short time from funding to excavation for detectors (2.5 years)
- All identified experiments accommodated
- Accepts large experiments high rock quality
- Valuable infrastructure from mine utilized
- Rapid environmental approval anticipated
- Robust funding profile guaranteed by the State
- Unprecedented State and local support