HEP Programs Michael Anerella

Superconducting Magnet Division



- LHC (CERN)
- LARP (CERN)
- ILC
- Magnet R&D (common coil)
- T2K Neutrino Experiment (JPARC)
- BTeV, MECO (RSVP) almost

Superconducting Magnet Division



LHC

- Based on 8cm 10M RHIC dipole coil
- 4 distinct production lines, 20 magnets total
- D1 "1-in-1" 8cm dipole (most like RHIC)
 - 1.8K operation (phase separator)
 - Oversized beam tube
- D2 "2-in-1" cold mass
 - Stainless steel collars
 - Oblate yoke / shell
 - CERN-style cryostat
 - > 20 tons
- D4 "2-in-1" cold mass
 - Similar to D2 but different aperture spacing
 - Converging beam tubes inside parallel coils
- D3 "2-in-1" cryostat
 - (2) RHIC-style dipoles in CERN-style cryostat







D3

SMD Directors Program Review 22June06

LARP (LHC Accelerator Research Program)

- Wind and React Nb₃Sn Coil R&D
 - 0.25M coil program for "tech transfer" from LBNL
 - 4M coil program to test length effects on reaction process



Superconducting Magnet Division



LARP

"Long Racetrack Coil R&D"

FY06

•Build and test (2) "subscale" (~ 12" long) double layer coils

 \rightarrow Use LBNL parts and tooling *

 \rightarrow Build BNL skills with W&R Nb₃Sn before committing expensive sums of superconductor

Design and build tooling & equipment for 4M W&R Nb3Sn coils

FY06 - FY07

•Build and test (2) 4M double layer coils

→Use LBNL support fixture*

→Test length effects using technology established w/subscale coils

* Collaborative effort

Superconducting Magnet Division







New LARP Major Equipment

- Cable re-spooling line
- Winding machine shuttle, clamps
- Reacting fixture
- Reacting oven
- Impregnation fixture
- Coil lifting fixture
- Lifting / up-righting fixture
- Prep / wiring station
- Assembly station









Superconducting Magnet Division



ILC (International Linear Collider)



• FY05: QD0 test coil completed & tested

- FY06:
 - Fabricate and test a short
 Octupole/Sextupole coil. Higher order magnetic elements require tighter bend radius onto a very small (20 mm) tube. This was non-trivial
 - Continue the 14 mrad conceptual design
 - Design "early tooling" for a 2m coil
 - Winding machine supports
 - Wrapping machine





Superconducting Magnet Division



ILC Beam Delivery System Magnet R&D - 3 Yr R&D Plan

- FY07
 - Detailed design of "Prototype" magnet system
 - Conceptual design of cryogenic (heat exchanger) & power lead systems
 - Design of assembly tooling
 - "early tooling" assembly
 - Construction of vibration test mock-up
 - Start Prototype quad coil fab
- FY08
 - Design of test tooling
 - Detailed design of cryogenics and power leads
 - Fab of prototype parts & tooling
 - Finish prototype quad coil fab, start prototype cold mass fab
 - Start prototype cold mass fab
- FY09
 - Finish fab of heat exchanger, test tooling
 - Finish prototype cold mass, cryostat fab
 - Cold test magnet

Superconducting Magnet Division



Nb3Sn React-and-Wind (HTS cable compatible technique) common coil magnet completed and measured this year. This marks the end of a multiyear Nb3Sn development program.







4 cm gap and ~ 10T at short sample





DCC017 during fabrication and en route to the Test Dewar





Superconducting Magnet Division



Vertical Dewar Cold Test Results



Superconducting Magnet Division





- First react-and-wind (R&W) Nb3Sn magnet* that has met (or even come close) to design parameters (i.e., REACHED CONDUCTOR LIMIT, with training). * magnet with aperture!
- Demonstrates that flat R&W coils work with this technique; no issues with extending to long coils.
- Erratic quench performance may have been due to the high level of energy deposition deposited into the coil during quenching,
- Program terminated for now due to budgetary considerations, BUT HOPE TO BUILD HTS RUTHERFORD CABLE INSERT COILS (SOON).

Superconducting Magnet Division



T2K (From Tokai To Kamioka Neutrino Oscillation Experiment)

- Direct Wind Correctors for KEK JPARC program
 - Initially combined function coils for inside bore of main combined function magnet (prototype delivered)
 - Reconfigured as 2 layer corrector, conduction cooled, for interconnect region (prototype delivered)
 - 3 production units to be made in FY07 DOE funds



Superconducting Magnet Division



BTeV, MECO (RSVP) - almost



MECO

- Several large sc solenoids for AGS RSVP
- \$3M+ assembly, test & integration by SMD
- Cost & schedule
- Detailed production plan
- Reviews at MIT



BTeV

- 16 multi-layer direct wind correctors for FNAL
- \$2M+ construction by SMD
- Magnetic design completed
- Test pattern wound
- Comprehensive cost, schedule, production plan
- FNAL, DOE Reviews at FNAL



Superconducting Magnet Division



Summary

- LHC Completed, all magnets meet requirements
- LARP ongoing; present program and funding limited; potential in upcoming years
- ILC huge opportunity to impact Beam Delivery System, much work to do
- Magnet R&D (common coil) painfully slow but gratifying progress so far; potential for additional R&D
- T2K (KEK, JPARC) good responsiveness to changing requirements; furthers global physics

