

# **NSLS-II Final Design Review**

## ***Spectroscopy Soft and Tender - SST1 and SST2***

***February 9, 2017***



***Dan Fischer***

***Leader Synchrotron Science Group***

***Materials Measurement Science Division***

***Material Measurement Laboratory***

***National Institute of Standards and Technology***

***“Promote Innovation and Enhance US Industrial Competitiveness”***

# ***NIST NSLS-II Partner Beamlines***

## ***NIST Synchrotron Science Group***

***Stationed at NSLS-II***

Ray Browning

Dan Fischer

Zugen Fu

Cherno Jaye

Barry Karlin

Johnny Kirkland

Bruce Ravel

Conan Weiland

Joe Woicik

Eliot Gann (NRC)

Nick Quackenbush (NRC)

w/Jean Jordan-Sweet (IBM)

w/Ron Jones MML/NIST Liaison

w/Ruben Reininger (SAS)

## ***NSLS-II***

Andy Broadbent

Zhong Zhong, Howard Robinson

John Fabijanac

Greg Fries

Chris Stebbins

ID, FE, EPS, Controls, Safety  
Groups

## ***FMB Oxford (UK)***

Andrew Fairley

Scott Mowat

FMB Team

# People create opportunities !



# 35 year NIST NSLS I/II Partnership

## Need

Development and optimization of advanced materials and innovative devices by U.S. industry requires measurement of electronic, chemical, and spatial structure at the nanoscale

## NIST NSLS-II Partner Beamline Suite

\$40M+ investment, started in 2009

### Spectroscopy Soft and Tender(SST) Beamlines

- 100 eV to 7.5 keV in a single experiment (common focus in 2 stations, rare capability)
- 2 full-field microscopes micro to nanoscale (unique magnetic projection design, SBIRs)


### Beamline for Materials Characterization(BMM)

Hard X-ray Absorption Spectroscopy and Diffraction 4.9 keV to 22 keV


Synchrotron Science Group (9) at BNL

## NSLS-I Achievements and Impact


- Spectroscopy beamlines that span the entire periodic table (90 experiments/year; 110 users)
- State-of-the-art X-ray and electron detectors
- In-situ capabilities for “real” samples/conditions




*NIST  $\mu$ -calorimeter X-ray detectors*



*Chemical imaging of designer photo voltaics*



*Ferroelectric SrTiO<sub>3</sub> thin film on Silicon*



*Photoelectron image of silk*

## Customers and Partners:

25 private, 14 public, 25 academic



# NIST NSLS-II Spectroscopy Beamline Suite spanning the entire periodic table (FY17)

*“We develop and apply new synchrotron X-ray measurement methods to establish structure-function relationships for advanced materials design”*

## Spectroscopy Soft and Tender (SST 1 and 2)


### *Soft and Tender Beamlines*

- 100 eV to 7.5 keV x-ray energy range
- Dual-beam endstations; rare capability
- Complete, non-destructive, depth selective measurement of electronic structure, chemistry, and bond orientation (NEXAFS and XPS)
- 3D Nanoscale XPS Microscopy
- Large area (2 x 2 cm) NEXAFS Microscopy (5  $\mu\text{m}$ )
- Outstanding Flux and Brightness

## Beamline for Material Measurement (BMM) 4.9 to 22 keV

### *XAFS and Diffraction*

- High flux: dilute samples, quick scanning for chemical reactions
- Focused beam: XAFS thin films, XAFS scan imaging
- High-energy resolution for enhanced chemical speciation
- 6-circle goniometer for high-resolution specular and non-specular diffraction



# SST and BMM User Communities

**SST**: NEXAFS, HAXPES, XPS, Microscopy    **BMM**: XAFS, Diffraction

**Communities or industries served**: inorganic and organic microelectronics, plastics, chemical / catalysis, biomaterials, batteries, environmental materials.

**Established User Community**: informed and prepared for operations

25 Academic, 25 Industrial,  
14 National Laboratory Groups



# SST Scope

- FOE Hutch
- Mechanical and Electrical Utilities
- EPS
- PPS
- Sources: EPU60 and U42
- Straight
- Front End
  
- Photon Delivery System with controls (FMB-O)
- End stations: HAXPES/NEXAFS,  $\mu$ XPS, HP NEXAFS/FY,  $\mu$ NEXAFS1, NEXAFS/XPS,  $\mu$ NEXAFS2 (NIST)
- Data acquisition and end station controls (NIST)

# SST construction project

*NSLS-II direct involvement in all aspects of construction, true partnership*

Andy Broadbent: NSLS-II Partner Beamline Portfolio Manager

Zhong Zhong and Howard Robinson : NSLS-II NIST Partner Beamline Manager

John Fabijanic: NSLS-II Designer

NIST/BNL Interagency Agreements fund BNL purchase and construction

IDs testing and integration; Straights and Front Ends (NSLS-II Groups; ID, FE, EPS, Controls)

Hutches/Common systems (NSLS-II Utilities)

Photon Delivery Systems – NIST Direct Purchases

Ruben Reininger optical designs, mirror specs

FMB Oxford/Berlin SST beamline mechanics, Diagnostics, PGM, DCM, mirrors, and installation



Experimental Stations – State of the art from NSLS-1 (at 7-ID)

SST1 – NEXAFS Microscope I & II, NEXAFS/XPS, Soft X-ray Emission Micro-calorimeter

*Funded Scope addition: Polarization-dependent Resonant Soft X-ray Scattering Station*

SST2 – HAXPES/NEXAFS, XPS Microscope, *future high pressure XAS*

# SST Schedule

**All activities finish Sept. 30, 2017, IRR in Oct.**

SST12 and BMM Partner Beamlines - 2016 December Draft	IPD - Summary Schedule		02-Feb-17 09:51		
Activity ID	Start	Finish	FY2016	FY2017	FY2018
			FY16	FY17	FY18
<b>SST 1&amp;2 Management</b>	02-Mar-15 A	15-Nov-17			
<b>SST 1&amp;2 Design</b>	02-Mar-15 A	28-Sep-17			
<b>SST 1&amp;2 Construction</b>	01-Oct-12 A	01-Sep-17			
<b>SST 1&amp;2 Hutches</b>	02-Mar-15 A	19-Sep-17			
<b>SST 1&amp;2 Utilities - Mechanical</b>	10-Mar-15 A	10-Oct-16 A			
<b>SST 1&amp;2 Utilities - Electrical</b>	10-Mar-15 A	20-Nov-15 A			
<b>SST 1&amp;2 EPS</b>	25-Apr-16 A	19-Apr-17			
<b>SST 1&amp;2 PPS</b>	16-Nov-15 A	28-Aug-17			
<b>SST 1&amp;2 Front End</b>	03-Aug-15 A	12-Jun-17			
<b>SST 1&amp;2 EPU60 Refurbishment</b>	03-Aug-15 A	19-Jun-17			
<b>SST 1&amp;2 U42 Refurbishment</b>	02-Nov-15 A	05-Jun-17			
<b>SST 1&amp;2 Straight</b>	29-Sep-15 A	05-Jul-17			
<b>SST 1&amp;2 Controls</b>	02-Nov-15 A	08-Sep-17			

# **Photon Delivery System**

## **History FMB-O SST FDRs at NSLS-II**

**(minutes, action items and responses posted)**

- Sept. 1, 2015 SST FDR: 8 action items
  - June 29, 2016 – NIST approves
- Sept. 13, 2016 FMB-O contract amendment  
Secondary Bremsstrahlung shielding and other shielding, diagnostics
- Nov. 29, 2016 FMB-O FDR: 13 action items
  - Dec. 21, 2016 NIST approves


# SST1&2 Layout: DCM, PGM, mirrors (14)



Current state of SST beamline component installation (30<sup>th</sup> December), all main optical elements are in position.

# SST1&2 Progress

- Beamline Photon Delivery System
  - **FMB-Oxford contract progressing well, although significant delay due to (NIST) contract modification.**
  - Installation Phase #1,2 completed, 3 mirrors, 2 monos installed. 2 precision slits and 7 hexapod mirror systems (9 mirrors) installed in Oct '16, some additional work completed Dec '16.
  - Some shielding analysis work completed (Zhong, Lee, Xia) and written up in the beamline PDR documents. **Requires further analysis by NSLS-II RSO (~Feb 2017).**
- Insertion Device and Straight
  - New control systems for the refurbished EPU60 and U42 devices are in progress.
  - Need to have devices plotted and checked for compatibility with NSLS-II as soon as possible. Magnetic measurement scheduled for Jan/Feb 2017.
  - Vacuum chamber is now installed (Dec '16 shutdown), see photo. Plan to install IDs in May 2017 shutdown.
- Front End
  - Manufacturing of mask and slit bodies in progress, everything else was installed in Dec 2017 shutdown.
- Infrastructure
  - Mechanical and electrical utilities completed (includes LN2 and exhaust systems).
  - PPS work in progress (mainly wiring for shutters and vacuum sensors and assembly of HMI panels).
  - EPS work in progress. Most wiring is now complete.



ID straight chamber installed.

# SST 1&2 Layout: Insertion Devices

- New control systems for refurbished EPU60 and U42 devices in progress Bldg. 842.
- Need to have devices plotted and checked for compatibility with NSLS-II ASAP. Magnetic measurement scheduled for Jan/Feb 2017.




ESRF U42 (Tender)



Aladdin EPU 60 (Soft)

# SST1&2 Layout: FOE, mirrors, and diagnostics




Beam

L1 Plane  
Tender

M1 Plane  
Soft


# SST1&2 Layout: FOE, mirrors, and diagnostics



# SST1&2 Layout: FOE, mirrors, diagnostics, and shielding

**Primary Bremsstrahlung**  
Radiation requirements that have become more rigorous than at the time of the contract award following the completion of the front end design by the NSLS II personnel


Additional mister masks have been added to protect downstream components from beams coming off L1 and M1 inside the FOE



**Secondary Bremsstrahlung**  
Radiation requirements that were not present at the time of FMB-Oxford contract award

**FMB Contract Amendment**

# SST1&2 Layout: PGM, DVM, mirrors, and diagnostics and pink beam shielding



In order to comply with the latest NSLS II Radiation Shielding requirements additional Pink beam transport shielding is required .

FOE

PGM

Elliptical Mirrors (Oct. 2016)  
M3C Soft to slit  
M3AB Soft Transfer to Slit

DCM

Soft Transfer to Slit


Soft Beam slit

**FMB Contract Amendment**


# SST1&2 Layout: PGM, DCM, operation modes

**PGM (100 – 2200eV)**  
**250, 600, 1200 I/mm**

**Special DCM 85° (1-7.5 keV)**  
**Si (111), (333), ~50meV**  
**Si (220), YB66**



# SST1&2 Layout: PGM, DCM, operation modes



# SST1&2 Layout: mirrors, op. modes, exp. stations and diagnostics

MicroXPS

L4 (tender 10micron) to MicroXPS

M4B (soft transfer 10micron) to MicroXPS

L3 (tender to L4 to MicroXPS)

HAXPES (tender L2A toroid FOE)


M4A Soft Beam to HAXPES  
Out to M4B to MicroXPS

Transfer line Soft Slit

Tender DCM

Soft Line Slit


**There are total 14 Mirrors!**  
**3 Positions with 2 mirrors**  
**2 Positions with pass through**  
**6 Exp. Stations, 9 shutters**




# SST1&2 Layout: op. modes and exp. stations



# SST1&2 Layout: op. modes and exp. stations



# SST1&2 Layout: op. modes, beam sizes and exp. stations



Soft X-ray Emission  
2 mm beam

NEXAFS Microscopes I and II  
Soft Dithered beams, 10mm<sup>2</sup> and 20mm<sup>2</sup>

NEXAFS/XPS  
Soft 35 micron

XPS Microscope (soft/tender)  
10 micron beams

HAXPES (soft/tender) 50 micron beams

# SST Safety

## ***BMM is a NIST NSLS-II Partner Beamline***


**Safety for Partner and Facility Beamlines is identical from conception, construction, commissioning and operations; this includes policies, training, equipment and procedures.**

- Andy Broadbent and Zhong Zhong (Howard Robinson) ensure that the NIST Partner Beamlines design and construction are fully compliant with all NSLS-II safety policies and practices.
- Dan Fischer (Lead Beamline Scientist) develop, monitor, and maintain safe operating conditions within the beamline during commissioning and operations.
- NSLS-II fully funds, designs, constructs, maintains and tests the beamline personnel protection systems.
- The NIST group has excellent safety track record of compliance, cooperation, and collaboration spanning 33 years of construction and operation of beamlines at NSLS.


# SST Safety Walk Thru:

- Burst Disks needed DCM, PGM, FOE components

- ✓ Egress path; duck under



- ✓ Static experimental gases on NEXAFS/XPS station w/approved barriers



- ✓ LN2 safety shut off on S8



- ✓ Gaseous N2 for bleed up w/BNL approved relief valves



- ✓ Static Magnetic Fields

NEXAFS Microscope 8T – Plexiglas exclusion zone

XPS Microscope 2T – High Field contained in small region inside 6” CFF cross