

## **SECTION 01575**

### **TEMPORARY EROSION AND SEDIMENTATION CONTROL**

#### **PART 1 GENERAL**

##### **1.01 SECTION INCLUDES**

- A. Prevention of erosion due to construction activities.
- B. Prevention of sedimentation of waterways, open drainage ways, and storm and sanitary sewers due to construction activities.
- C. Restoration of areas eroded due to insufficient preventive measures.

##### **1.02 RELATED SECTIONS**

- A. See Section 01352 - LEED Requirements, for overall project goals relating to environment and energy.
- B. Section 02300 - Site Preparation: Limits on clearing; topsoil stripping; disposition of vegetative clearing debris; and grading.

##### **1.03 REFERENCES**

- A. EPA 832-R-92-005 - Storm Water Management for Construction Activities; U.S. Environmental Protection Agency; 1992.
- B. USDA TR-55 - Urban Hydrology for Small Watersheds; USDA Natural Resources Conservation Service; 1986.

##### **1.04 PERFORMANCE REQUIREMENTS**

- A. Comply with all requirements of U.S. Environmental Protection Agency for erosion and sedimentation control.
- B. Install soil erosion and sediment control devices prior to the start of any clearing, grubbing, or excavation. Clearing, grubbing, or excavation shall not start without authorization from BNL.
- C. Best Management Practices Standard: EPA 832-R-92-005.
- D. Develop and follow an Erosion and Sedimentation Prevention Plan (ESPP) and submit periodic inspection reports.
- E. Do not begin clearing, grading, or other work involving disturbance of ground surface cover until ESPP has been approved by MPO.
- F. Timing: Put preventive measures in place as soon as possible after disturbance of surface cover and before precipitation occurs.
- G. Storm Water Runoff: Control increased storm water runoff due to disturbance of surface cover due to construction activities for this project.
  - 1. Prevent runoff into storm and sanitary sewer systems, including open drainage channels, in excess of actual capacity or amount allowed by authorities having jurisdiction, whichever is less.
  - 2. Anticipate runoff volume due to the most extreme short term and 24-hour rainfall events that might occur in 25 years.
- H. Erosion On Site: Minimize wind, water, and vehicular erosion of soil on project site due to construction activities for this project.
  - 1. Control movement of sediment and soil from temporary stockpiles of soil.
  - 2. Prevent development of ruts due to equipment and vehicular traffic.
  - 3. If erosion occurs due to non-compliance with these requirements, restore eroded areas at no cost to Owner.

- I. Erosion Off Site: Prevent erosion of soil and deposition of sediment on other areas caused by water leaving the project site due to construction activities for this project.
  - 1. Prevent windblown soil from leaving the project site.
  - 2. Prevent tracking of mud onto roads outside site.
  - 3. Prevent mud and sediment from flowing onto sidewalks and pavements.
  - 4. If erosion occurs due to non-compliance with these requirements, restore eroded areas at no cost to Owner.
- J. Sedimentation of Waterways On Site: Prevent sedimentation of waterways on the project site, including rivers, streams, lakes, ponds, open drainage ways, storm sewers, and sanitary sewers.
  - 1. If sedimentation occurs, install or correct preventive measures immediately at no cost to Owner; remove deposited sediments; comply with requirements of authorities having jurisdiction.
  - 2. If sediment basins are used as temporary preventive measures, pump dry and remove deposited sediment after each storm.
- K. Open Water: Prevent standing water that could become stagnant.
- L. Maintenance: Maintain temporary preventive measures until permanent measures have been established.

## **1.05 SUBMITTALS**

- A. See Section 01300 - Submittals, for submittal procedures.
- B. Erosion and Sedimentation Control Plan:
  - 1. Submit within 2 weeks after Notice to Proceed.
  - 2. Include:
    - a. Site plan (all work on 24"x36" min.) identifying soils and vegetation, existing erosion problems, and areas vulnerable to erosion due to topography, soils, vegetation, or drainage.
    - b. Site plan showing grading; new improvements; temporary roads, traffic accesses, and other temporary construction; and proposed preventive measures.
    - c. Where extensive areas of soil will be disturbed, include storm water flow and volume calculations, soil loss predictions, and proposed preventive measures.
    - d. Schedule of temporary preventive measures, in relation to ground disturbing activities.
    - e. Other information required by law.
    - f. Format required by law is acceptable, provided any additional information specified is also included.
  - 3. Obtain the approval of the Plan by Owner.
- C. Certificate: Mill certificate for silt fence fabric attesting that fabric and factory seams comply with specified requirements, signed by legally authorized official of manufacturer; indicate actual minimum average roll values; identify fabric by roll identification numbers.
- D. Inspection Reports: Submit report of each inspection; identify each preventive measure, indicate condition, and specify maintenance or repair required and accomplished.
- E. Maintenance Instructions: Provide instructions covering inspection and maintenance for temporary measures that must remain after Substantial Completion.

## **PART 2 PRODUCTS**

### **2.01 MATERIALS**

- A. Mulch: Use one of the following:
  - 1. Straw or hay.
  - 2. Wood waste, chips, or bark.
- B. Seed:
  - 1. Seed shall be quick growing ryegrass or approved equivalent, suitable to the area being protected.
- C. Bales: Air dry, rectangular straw bales.
  - 1. Cross Section: 14 by 18 inches, minimum.
  - 2. Bindings: Wire or string, around long dimension.
- D. Bale Stakes: One of the following, minimum 3 feet long:
  - 1. Steel U- or T-section, with minimum mass of 1.33 lb per linear foot.
  - 2. Wood, 2 by 2 inches in cross section.
- E. Silt Fence Fabric: Polypropylene geotextile resistant to common soil chemicals, mildew, and insects; non-biodegradable; in longest lengths possible; fabric including seams with the following minimum average roll lengths:
  - 1. Average Opening Size: 30 U.S. Std. Sieve, maximum, when tested in accordance with ASTM D 4751.
  - 2. Width: 30"
  - 3. Permittivity:  $0.05 \text{ sec}^{-1}$ , minimum, when tested in accordance with ASTM D 4491.
  - 4. Ultraviolet Resistance: Retaining at least 70 percent of tensile strength, when tested in accordance with ASTM D 4355 after 500 hours exposure.
  - 5. Tensile Strength: 100 lb-f, minimum, in cross-machine direction; 124 lb-f, minimum, in machine direction; when tested in accordance with ASTM D 4632.
  - 6. Elongation: 15 to 30 percent, when tested in accordance with ASTM D 4632.
  - 7. Tear Strength: 55 lb-f, minimum, when tested in accordance with ASTM D 4533.
  - 8. Color: Manufacturer's standard, with embedment and fastener lines preprinted.
  - 9. Connectors shall be tie wires, nylon tie-wraps, or approved equivalent.
- F. Silt Fence Posts: One of the following, minimum 5 feet long:
  - 1. Steel U- or T-section, with minimum mass of 1.33 lb per linear foot.
  - 2. Softwood, 4 by 4 inches in cross section.
  - 3. Hardwood, 2 by 2 inches in cross section.
- G. Sand Bags:
  - 1. Sand bags shall be made from reinforced plastic and shall include ties. Sand shall be used as a fill material and shall be double bagged with separate ties for each bag, in order to prevent leakage.
- H. Turbidity Curtain:
  - 1. Turbidity curtain shall consist of a geotextile, flotation device, and anchoring system.
- I. Gravel: See Section 02057 for aggregate.

## **PART 3 EXECUTION**

### **3.01 EXAMINATION**

- A. Examine site and identify existing features that contribute to erosion resistance; maintain such existing features to greatest extent possible.

### **3.02 PREPARATION**

- A. Schedule work so that soil surfaces are left exposed for the minimum amount of time.

### **3.03 SCOPE OF PREVENTIVE MEASURES**

- A. In all cases, if permanent erosion resistant measures have been installed temporary preventive measures are not required.
- B. Construction Entrances: Traffic-bearing aggregate surface.
  - 1. Width: As required; 20 feet, minimum.
  - 2. Length: 50 feet, minimum.
  - 3. Provide at each construction entrance.
  - 4. Where necessary to prevent tracking of mud onto roads, provide wheel washing area out of direct traffic lane, with drain into sediment trap or basin.
- C. Linear Sediment Barriers: Made of silt fences.
  - 1. Provide linear sediment barriers:
    - a. Along downhill perimeter edge of disturbed areas, including soil stockpiles.
  - 2. Space sediment barriers with the following maximum slope length upslope from barrier:
    - a. Slope of Less Than 2 Percent: 100 feet..
    - b. Slope Between 2 and 5 Percent: 75 feet.
    - c. Slope Between 5 and 10 Percent: 50 feet.
    - d. Slope Between 10 and 20 Percent: 25 feet.
    - e. Slope Over 20 Percent: 15 feet.
- D. Storm Drain Curb Inlet Sediment Trap: Protect each curb inlet using one of the following measures:
  - 1. Filter fabric wrapped around hollow concrete blocks blocking entire inlet face area; use one piece of fabric wrapped at least 1-1/2 times around concrete blocks and secured to prevent dislodging; orient cores of blocks so runoff passes into inlet.
  - 2. Straw bale row blocking entire inlet face area; anchor into pavement.
- E. Storm Drain Drop Inlet Sediment Traps: As detailed on drawings.
- F. Temporary Splash Pads: Stone aggregate over filter fabric; size to suit application; provide at downspout outlets and storm water outlets.
- G. Soil Stockpiles: Protect using one of the following measures:
  - 1. Cover with polyethylene film, secured by placing soil on outer edges.
  - 2. Cover with mulch at least 4 inches thickness of pine needles, sawdust, bark, wood chips, or shredded leaves, or 6 inches of straw or hay.
- H. Mulching: Use only for areas that may be subjected to erosion for less than 6 months.
  - 1. Wood Waste: Use only on slopes 3:1 or flatter; no anchoring required.
- I. Temporary Seeding: Use where temporary vegetated cover is required.

### **3.04 INSTALLATION**

- A. Maintain all soil erosion and sediment control devices.
- B. Inspect regularly and at the direction of the MPO Construction Representative.
- C. Remove any sediment buildup or as directed by the MPO Construction Representative.

- D. Traffic-Bearing Aggregate Surface:
  - 1. Excavate minimum of 6 inches.
  - 2. Place geotextile fabric full width and length, with minimum 12 inch overlap at joints.
  - 3. Place and compact at least 6 inches of 1.5 to 3.5 inch diameter stone.
- E. Silt Fences:
  - 1. Store and handle fabric in accordance with ASTM D 4873.
  - 2. Where slope gradient is less than 3:1 or barriers will be in place less than 6 months, use nominal 16 inch high barriers with minimum 36 inch long posts spaced at 6 feet maximum, with fabric embedded at least 4 inches in ground.
  - 3. Where slope gradient is steeper than 3:1 or barriers will be in place over 6 months, use nominal 28 inch high barriers, minimum 48 inch long posts spaced at 6 feet maximum, with fabric embedded at least 6 inches in ground.
  - 4. Where slope gradient is steeper than 3:1 and vertical height of slope between barriers is more than 20 feet, use nominal 32 inch high barriers with woven wire reinforcement and steel posts spaced at 4 feet maximum, with fabric embedded at least 6 inches in ground.
  - 5. Install with top of fabric at nominal height and embedment as specified.
  - 6. Do not splice fabric width; minimize splices in fabric length; splice at post only, overlapping at least 18 inches, with extra post.
  - 7. Fasten fabric to wood posts using one of the following:
    - a. Four 3/4 inch diameter, 1 inch long, 14 gage nails.
    - b. Five 17-gage staples with 3/4 inch wide crown and 1/2 inch legs.
  - 8. Fasten fabric to steel posts using wire, nylon cord, or integral pockets.
  - 9. Wherever runoff will flow around end of barrier or over the top, provide temporary splash pad or other outlet protection; at such outlets in the run of the barrier, make barrier not more than 12 inches high with post spacing not more than 4 feet.
- F. Straw Bale Rows:
  - 1. Install bales in continuous rows with ends butting tightly, with one bale at each end of row turned uphill.
  - 2. Install bales so that bindings are not in contact with the ground.
  - 3. Embed bales at least 4 inches in the ground.
  - 4. Anchor bales with at least two stakes per bale, driven at least 18 inches into the ground; drive first stake in each bale toward the previously placed bale to force bales together.
  - 5. Fill gaps between ends of bales with loose straw wedged tightly.
  - 6. Place soil excavated for trench against bales on the upslope side of the row, compacted.
- G. Mulching Over Large Areas:
  - 1. Dry Straw and Hay: Apply 2-1/2 tons per acre; anchor using dull disc harrow or emulsified asphalt applied using same spraying machine at 100 gallons of water per ton of mulch.
  - 2. Wood Waste: Apply 6 to 9 tons per acre.

### **3.05 MAINTENANCE**

- A. Inspect preventive measures weekly, within 24 hours after the end of any storm that produces 0.5 inches or more rainfall at the project site, and daily during prolonged rainfall.
- B. Repair deficiencies immediately.
- C. Silt Fences:
  - 1. Promptly replace fabric that deteriorates unless need for fence has passed.
  - 2. Remove silt deposits that exceed one-third of the height of the fence.
  - 3. Repair fences that are undercut by runoff or otherwise damaged, whether by runoff or other causes.
- D. Straw Bale Rows:
  - 1. Promptly replace bales that fall apart or otherwise deteriorate unless need has passed.
  - 2. Remove silt deposits that exceed one-half of the height of the bales.

- 3. Repair bale rows that are undercut by runoff or otherwise damaged, whether by runoff or other causes.
- E. Clean out temporary sediment control structures weekly and relocate soil on site.
- F. Place sediment in appropriate locations on site; do not remove from site.

### **3.06 CLEAN UP**

- A. At the completion of all construction work, remove soil erosion and sediment control devices, unless directed otherwise by BNL. Verify that site drainage works properly, fine grading is complete, and final seeding has been completed. BNL reserves the right to require the contractor to maintain all soil erosion and sediment control devices until permanent soil erosion and sediment control is installed and functional.
- B. Clean out temporary sediment control structures that are to remain as permanent measures.
- C. Where removal of temporary measures would leave exposed soil, shape surface to an acceptable grade and finish to match adjacent ground surfaces.

### **END OF SECTION**

Revision History	
Date	Rev. No.
02-19-09	0